



# LORAIN COUNTY ENGINEER

*KEN CARNEY, P.E., P.S.*

November 6, 2015

Attn: Bidder

Re: King-Kobelt Ditch  
LaGrange Township

The Lorain County Storm Water District is soliciting bids for clearing the King-Kobelt Ditch in LaGrange Township. We anticipate this work would begin sometime in early 2016.

If interested please complete the attached proposal form and return to the Lorain County Engineer's Office by 3:30 P.M. on Friday, December 4, 2015. Enclosed are the specifications for the work and a site plan for the project.

Please contact Linda Eckhart at 440-329-5590 if you have any questions.

Sincerely,

Ken Carney  
Lorain County Engineer

cc: Mark Haynes Construction  
Carl Wesemeyer Construction  
Hanko Farms  
Cross Roads Asphalt Recycling, Inc.  
Big Trees  
Haynes Land Improvement  
Edwards Land Clearing  
Don Romancak, Storm Water District ✓  
File

Z:\Word Data\2015\SWAC\11-06-15 To Bidders re - King-Kobelt Ditch-LaGrange Township clearing proposals due 12-04-15 by 3.30 PM.doc



**INVITATION TO BID  
LORAIN COUNTY BOARD OF COMMISSIONERS**

**FUND:** Storm Water District      **ACCOUNT:** \_\_\_\_\_

<b>DELIVER TO: (Charges included):</b> Lorain County Engineers Office 247 Hadaway Street Elyria, Ohio 44035	<b>Mail Invoice to:</b>  SAME
--	-------------------------------------

**Bid submitted by:**

Company name: _____	Bid due date: 4-Dec-15
Address: _____	Time: 3:30 PM
City/State: _____	<b>Address Bids to:</b> Lorain County Engineers Office 247 Hadaway Street Elyria, Ohio 44035 Att: Bill Holtzman
Signature: _____	
Title: _____ Date: _____	
Phone: _____ Fax: _____	

**For further bid information contact:** Linda Eckhart      **Phone:** 440-329-5590

QUANTITY	UNIT	MATERIAL, SUPPLIES, EQUIPMENT OR SERVICE	UNIT \$	TOTAL BID
Lump Sum	LS	King Kobelt Ditch Project : Phase #1 Clearing		
		<b>ENGINEER'S ESTIMATE: \$64,000.00</b>		

**DELIVERY AND DISCOUNT TERMS:** Will deliver within \_\_\_\_\_ calendar days  
Cash discount terms: \_\_\_\_\_ % within \_\_\_\_\_ days.

**AWARD RECOMMENDATION**

**DATE:** \_\_\_\_\_      **PURCHASE ORDER #** \_\_\_\_\_

**King Kobelt Ditch Project**  
**Phase 1**  
**LaGrange Township**  
**November 4, 2015**

**Project Location:** Ditch Clearing begins at Parsons Road just east of SR 301 and runs south for 10,484 ft to Biggs Road. The Lateral runs approximately 500 Ft South of Parsons Road; westerly to S.R. 301 for 1,750 ft. for a Total of 12,234 LF. (Red Line on the attached Aerial).

**Proposed Work:** The proposed work shall consist of clearing all trees and brush within the ditch and along one side of the ditch bank and a minimum of 20 ft. on the top of the bank (unless otherwise designated). All stumps shall be cut flush with the existing ground and all trees and brush shall be chipped up and disposed of onsite as approved by the Township.

The Contractor shall grade any disturbed areas to allow for natural drainage into the ditch by the surrounding watershed along the proposed limits of the project.

One side of the ditch shall be adequately clear of trees and brush and graded to allow the County's mower to traverse through the project for future maintenance.

**Applicable Specifications:** All work shall be performed in accordance with the following ODOT specifications (current edition) unless modified herein.

Item 201      Clearing and Grubbing  
Item 670      Erosion Protection

**Modifications:**

- The Contractors shall provide ditch checks, silt fence or other measures as appropriate to control erosion from the disturbed site.

**Payment:** The work under this project shall be paid at the lump sum price bid for the King Kobelt Ditch Project which shall include all clearing and grubbing, grading of disturbed areas, erosion control and other incidental items as required to complete the project.

**Timeline:** The work shall be completed within 60 days of Issuance of a Notice to Proceed.

**Estimate:** \$64,000.00

